FOR MYSORE STATE

1 10 50.

PUBLIC WORKS (195 4) Department.

MS SERIES.

G.O. NO. 2030

Dated 7-6-1954

[Despatch Abstract.]

PORTS - Mangalore - Provision of electric lights in goods sheds A & B at North Quay - Estimate for Rs.1,350/- Sanctioned.

From:
L.H.Cornish Esq.,
State Port Officer,
P.B.No.13,
Madras-1.

To:
The Secretary to Government,
Public Works Department,
Madras.



No.160 SD/54-9 dated 26th May 1954

Sir,

Ports - Mangalore - Special repairs to goods shed A & B - Providing electric lights in port godowns North quay - Estimate Rs.1350/- - Forwarded.

43473

I forward herewith for the sanction of Government an estimate amounting to Rs.1,350/- for the work of special repairs to goods shed "A" and "B" Providing electric lights in port godowns north quay at the port of Mangalore. The report accompanying the estimate explains the necessity for the work.

2. Necessary provision for the work has been made in the current year's draft budget estimate of the Mangalore Landing and Shipping Fund 1954-55 under print for being submitted to Government.

Yours faithfully,

State Port Officer.

Encl: 1 estimate in duplicate.
AT/28.

M. F. 4—50M—7-8-49.

ESTIMATE FORM—Detail Measurements, etc.

Detail of work. (1)	Number. (2)	Measurements in feet. Length. (3)	Breadth. (4)	Depth. (5)	Area or contents. (6)	Total quantity of each description of work. (7)
Providing Electric Lights in Port Godowns A & B - North quay, Mangalore Port 1954-55.						
Northern shed - Shed A.						
(1) Extending U.G. Mains protection from the Pole to the Godown a distance of 35 feet, road cutting, closing etc. all included.	35 Rft.				35 Rft.	35 Rft.
(2) Supplying 4 - 40 Watts tube lights G.E.C.with G.E.C.Chokke and condenser.	4				4	4 Nos.
(3) Supplying materials and wiring for 4 light points in the Godown.	4 light points.				4	4 light points.
(4) Supplying and fixing one Chambarton Moobam (G,E.C. net samps)	1 No.				1 No.	1 No.
(5) Supplying and fixing one I.C.D.P.Switch in the Godown 15 AMPS.	1 No.				1 No.	1 No.
Southern shed - Shed No.B.						
(1) Extension of mains from the closed shed North to South about 100 ft. dist. 2-3/20 Vr. W.P. Cables ...	100 Rft.				100 Rft.	100 Rft.
(2) Supplying five Nos. 40 Watts tube lights G.E.C. with G,E.C. with G.E.C. Choke and condenser.					5	5 Nos.
(3) Supplying materials and wiring for 5 light points.	5 light points				5	5 light points.
(4) Supplying and fixing One I.C.D.P.Switch	1 No.				1	1 No.
(5) Unforeseen items, sales tax etc.					L.S.	L.S.

A.J.John,
S.O.K. 19-4-1954.

Report to accompany the estimate for providing Electric Lights in Port Godowns A & B at North Quay, Mangalore Port.

Amount of estimate Rs.1,350/-

The estimate provides for supplying and fixing 9 Nos. - 40 Watts tube lights in sheds A & B at North quay (Shed A - 4 Nos, and shed B 5 Nos. lights) to give more facilities during loading and unload ng of cargoes. Supplying iron materials and wiring for 9 light points, extending U.G.Main protection from the existing Pole etc. are provided in the estimate for proper completion of the work. The rates are based on the quotations of the Modern Engineering Works, Mangalore. Quotations also are attached.

A.J.John,
S.O.K. 19-4-54.

Mangalore, 24-4-54. ASSISTANT ENGINEER (MARINE) 28.5.54

Port Officer. 24/4

P.W.D. V-13—Inner—23,448—16-10-41 (3) (E. No. 31)

ESTIMATE FORM—Abstract.

Item number. (1)	Quantity. (2)	Description of work. (3)	Rate. (4)	Per (5)	Amount. (6)	Total. (7)
			Rs.		Rs.	Rs.
		Providing Electric lights in the Port Godowns A. & B. North Quay - Mangalore Port 1954-55.				
		NORTHERN SHED - SHED 'A'.				
1.	35 Rft.	Extending U.C.mains protection from the Pole to the Godown a disbance of 35 feet road cutting, closing etc, all included.	35 Rft.		200	
2.	4 Nos.	Supplying 4-40 Watts tube lights G.E.C. with G.E.C. Choke and condenser.	70/-	each	280	
3.	4 Light points.	Supplying materials and wiring for 4 light points in the godown	30/-	each	120	
4.	1 No.	Supplying and fixing one chambertan and Hoobam (G.E.C. and 5 amps.)	50/-	"	50	
5.	1 No.	Supplying and fixing one switch in the Godown 15 amps.	20/-	each	20	
		SOUTHERN SHED - SHED 'B'.				
1.	100 Rft.	Extension of mains from the closed shed North to South about 100 feet dist. 2-3/20 Rd.W.P.Cables.	1-0-0	1 Rft.	100	
2.	5 Nos.	Supplying five Nos. 40 watts. tube lights G.E.C. with G.E.C.	70/-	each	350	
3.	5 Light points,	Supplying materials and wiring for 5 light points. ...	30/-	each	150	
4.	1 No	Supplying and fixing one I.C.D.P.Switch	20/-	each	20	
5.	L.S.	Unforeseen items sale-tax etc.			60	
		Grand total of estimate			1350	

(Sd) A.J.John,
S.O.K.19-4-54.

Port office, Mangalore I.)
P.B.No.146.)
Dated 24th April 1954.)

NA.24/4.

Port Officer.

COUNTERSIGNED.

28-5-54
ASSISTANT ENGINEER (MARINE)

STATE PORT OFFICER

ESTIMATE FORM—Abstract.

Item number (1)	Quantity. (2)	Description of work. (3)	Rate. (4)	Per (5)	Amount. (6)	Total. (7)
			RS.		RS.	RS.

District: South Kanara.

Port: Mangalore.

A | Head of charge:- Mangalore Landing & Shipping Fund 1954-55.

Name of Work - Special repairs to Goods-shed 'A' & (B' - Providing Electric Lights in Port Godowns A & B. North quay, Mangalore Port.

Amount of Estimate - Rs.1,350/-.

To be carried out by - Port Department.

Budget Provision:- Mangalore Landing and Shipping Fund - Rs.1500/- has been provided in the draft Budget Estimate of the Mangalore Landing and Shipping Fund for 1954-55.

P.W.D.(R)

C.No. 43473F/54.

Ports - Mangalore - Provision of electric lights in goods sheds A & B at north quay - Estimate for Rs. 1,350/- - Sanctioned.

From the S.P.O Letter No. 1605D/54-9 dt 26.5.54.

G.O.Ms.No. 2030 P.W. dt 7 ——— 6.1954.

The Govt. sanction the estimate for Rs1,350/- (Rupees one thousand three hundred and fifty only) for the provision of electric lights in goods sheds A & B at the north quay at the Port of Mangalore.

The expenditure is debitable to the Mangalore Landing and Shipping Fund.

5.6.54

Dd 2t. 140 8.6.54 Dms

To The S.P.O with enclo.
To the Ex. & L-F. Accts.
S/C-2